CHITALDROOG DIVISION.

[ADVERTISEMENT.

The 17th July 1895.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Chitaldrug Division, up to 31st August 1895, for constructing a new tank near Mustalgummi, Challakere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1897.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A. M. and 4 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank near Mustalgummi, Challakere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Items of work	*Per.*	*Quantity.*
Bund—		
Earthwork (special)	C. yd.	31,919
Clay puddling	,,	1,382
Clearing silt	,,	2,002
Cutting jungle	L. S.	
New stone work	C. yd.	2,296
Grade stones	No.	20
B. M. stones	No.	2
Gauge stone	No.	1
Tank No. stone	No.	1
Turfing	S. yd.	6,790
Total...		
Sluice Nos. 1 & 2—		
Brick in ordinary mortar	C. ft.	2,538
Burnt stone slabs dressed	S. ft.	68
Ditto undressed	,,	570
Plastering with mortar	Sqr.	9·96
Earthwork	C. yd.	270
Gibbet stones dressed	No.	4
Total for 2 sluices..		
Waste Weir—		
Brick in mortar	C. ft.	1,055
Burnt stone slabs dressed	S. ft.	225
Ditto undressed	,,	366
Rough stone work	C. yd.	40
Ditto Sujicut	,,	270
Earthwork	,,	589
Plastering with mortar	Sqr.	11·61
Total..		

K. PRAHALNADA RAO, *Offg. Executive Engineer.*

IN THE CHIEF COURT OF MYSORE AT BANGALORE.

Mis. Application No. 1 *of* 1895.

Mr. John C. S. Lawrance, B.A., L.L.B., Advocate, residing in Infantry Road, Bangalore. *Applicant.*

In the matter of the estate of the late Lieut. Richmond Allen FitzGibbon .. *Deceased.*

Whereas the abovenamed applicant, as Attorney of Fitz Gibbon, Lieut., of 91 Queen Street, Auckland, New Zealand in Australia, has applied to this Court for letters of Administration to administer the estate of the said Lieut. Richmond Allen FitzGibbon, formerly of Her Majesty's Indian Army who died in Duke Street, Portland Place, in the county of Middlesex on the 31st of July 1871, and that Friday the 26th day of July 1895 at 11 A. M., has been fixed for the hearing of the application.

All persons claiming to have any interest in the estate of the deceased are hereby called upon to come and see the proceedings on or before the said 26th day of July 1895.

Given under my hand and the seal of the Court this 17th day of June 1895.

By order of the Court,

V. A. RAJARATNA MUDALIAR,

Deputy Registrar, doing duty as Registrar.